

DOVER ARTIFICIAL LIFT TMX®

Truck Mounted X-celerator®

The Truck Mounted X-celerator® (TMX) is a versatile piece of well servicing equipment that has a closed loop hydraulic system and has been specially designed for running continuous coiled rod of all sizes. The standard TMX unit comes with a Sucker Rod BOP, Safety Brake, Rod Stripper and Fireblade™ Welder. The TMX unit is able to adapt and work with any other onsite well servicing rig, FBU, or unit requiring continuous rod support. The unit is capable of repairing continuous failed rod strings as well as installing custom length strings, tapered rod strings and welding pin ends all to our customers specifications.

The TMX is a cost savings on its own with the ability to service multiple well sites in a short time, with minimal surface imprint and a quick rig up and rig out time along with minimal support staff. The applications for this specific unit are as follows but not limited to pulling and running continuous rod strings, fishing, changing out PCP, plunger, and insert pumps and running diagnostic tools for down hole applications.



X-250		
Maximum Pull (lbs)	Maximum Speed (ft/min)	Depth Counter System
30,000	120	Electronic & Manual

X-350		
Maximum Pull (lbs)	Maximum Speed (ft/min)	Depth Counter System
50,000	120	Electronic & Manual

X-450 (Open Faced)		
Maximum Pull (lbs)	Maximum Speed (ft/min)	Depth Counter System
50,000	100	Electronic & Manual



NPS Middle East LLC.
 PO Box 1429, Ruwi 112
 Muscat Oman

doverals.com